

CITY OF STONECREST

ACKNOWLEDGE RECEIPT OF ADDENDUM #1 FORM

**ITB #2020-001
2020 Street Resurfacing**

Upon receipt, please print and add to your proposal

I hereby acknowledge receipt of the supplement pertaining to the above referenced bid.

COMPANY NAME: _____

CONTACT PERSON: _____

ADDRESS: _____

CITY: _____ **STATE:** _____ **ZIP:** _____

PHONE: _____ **FAX:** _____

EMAIL ADDRESS: _____

SIGNATURE

DATE

ADDENDUM #1

ITB #2020-001 2020 Street Resurfacing

Questions Received (answers in RED):

1. There is a discrepancy on the Bid Bond and Performance Bond amounts. Page 6 requires the Bid Bond in the amount of the total bid. Page 41 states that the Performance Bond and Bid Bond is for the total amount of the contract. Please clarify.

The numbers are incorrect on page 6. The bid bond is for 5% of the bid amount. The performance bond will be for 100% of the amount of the successful contract.

2. Do you anticipate extending the bid due date?

It is not anticipated at this time that the bid date will be extended.

3. What additional details are you willing to provide, if any, beyond what is stated in bid documents concerning how you will identify the winning bid?

Staff will recommend that the bid be awarded to the lowest qualified bidder meeting all of the mandatory requirements. The final approval of the contract is by the City of Stonecrest Mayor & Council.

4. Was this bid posted to the nationwide free bid notification website at www.mygovwatch.com?

No, the bid was posted on the City's website, in the newspaper, and on Georgia Procurement Registry site (BidNet).

5. Other than your own website, where was this bid posted?

See response to Question #4 above.

6. Bid items #6 and 7 include tack. Items 3,4,5 do not. Will a separate bid item for the required tack be added in an addendum?

No, tack should be included in the unit pricing for items #3 thru #5

7. Can you please tell me what depths in inches will be required for the 19 MM and 12.5 MM asphalt, please? The 9.5 MM is stated as 1.25" and 2" lifts.

The minimum lift for 19mm is 1-3/4". 12.5mm is to be placed at 1-3/8". 9.5 mm is to be placed at 1-1/4".

8. Mall Parkway is shown to have 2.356 tons of 9.5mm. Is this correct?

No, Mall Parkway should be 12.5mm. This will not change the overall bid quantities.

9. What is the thickness for the 19mm, 9.5mm, and 12.5mm?

See #7 above.

10. What Type I or II for the 9.5mm?

Type II

11. For all the major roads listed on Page 17: What is the typical section?

Mill 3", patch, install 1-3/4" of 19mm and 1-3/8" of 12.5mm.

12. With the necessary for lane closures and Message Boards will there be a

reconsideration for a separate Traffic Control pay item?

There is no line item for traffic control. Traffic control should be included in your overall bid pricing.

13. Will all of the Asphalt items include tack? Or will there be consideration for a tack coat pay item?

See #6 above.