

DATE: July 8, 2019

TO: All Bidders

FROM: City of Stonecrest Procurement Department

RE: ITB No. 2019-017, 2019 Street Resurfacing – Phase 2

Please see Addendum No. 2 for the above-referenced solicitation.

ADDENDUM NO. 2 ITB NO. 2019-017 2019 STREET RESURFACING – PHASE 2

A. The following change has been made to the above- referenced solicitation:

Delete Page 1-4 REVISED 07/08/2019 Page 1-4 – Corrected bid number



ADDENDUM NO. 2 ITB NO. 2019-017 2019 STREET RESURFACING – PHASE 2 REVISED 7/8/2019

DATE: July 8, 2019

TO: All Bidders

FROM: City of Stonecrest Procurement Department

RE: ITB No. 2019-014 ITB No. 2019-017, 2019 Street Resurfacing – Phase 2

Please see Addendum No. 1 for the above-referenced solicitation.

ADDENDUM NO. 1 ITB NO. 2019-014 ITB NO. 2019-017 2019 STREET RESURFACING – PHASE 2

- A. The following are questions received and City of Stonecrest responses for the above-referenced solicitation:
 - 1. Will earth shoulder rutting on the roadways listed need to be repaired? No. Shoulder repair is not included in the scope of work.
 - 2. Is the existing pavement section enough to mill down 3 inches and patch at 4 inches? Or will we hit GAB or dirt?
 - We have not done cores, but you may hit GAB at a depth of 7 inches.
 - 3. Will the existing construction project on Salem Road be marked, so we know where to tie the Full Reclamation?
 - The construction project on Salem Road will tie in at the GDOT construction limit. We will mark the tie-on point.
 - 4. Are the turn lanes for the subdivision side streets included to be milled and paved? Yes. They are included in the quantities.
 - On Thompson Mill Road, do we go to the bridge at the City limits or tie to the new pavement joint before the bridge?
 Tie to the new pavement joint.
 - 6. What are the working hours?
 - Monday thru Friday 9 a.m. to 4 p.m. Weekend work will probably be allowed but need to be reviewed by the City.
 - 7. Is the sequence mill patch 19mm, 12.5mm? Will we need to cover the milling with at least the 19mm to keep the drop off at 1.25 inches?
 - This sequence is correct. Yes, the 3" milling cannot be exposed and must have the 19mm installed shortly after milling. Construction should be phased accordingly.
 - 8. What the available work hours and lane closure hours will be for this project? **Please see question #6.**
 - 9. What is the above project's estimate cost/value or budget? **Approximately \$2 million.**

ADDENDUM NO. 1 1TB NO. 2019-014 1TB NO. 2019-017 2019 STREET RESURFACING – PHASE 2

B. The following change has been made to the above referenced solicitation.

Delete: Page 19 Bid Schedule

Add: Revised 07/02/2019 Page 19 Bid Schedule

C. All other terms and conditions remain the same.

2019 STREET RESURFACING – PHASE 2 ADDENDUM NO. 1 ITB NO. 2019-014 ITB NO. 2019-017 REVISED, 07/02/2019, PAGE 19

ITEM #	DESCRIPTION	UNIT	APPROX. QUANTITY	UNIT PRICE	TOTAL AMOUNT
1.	Traffic Control	LS	1	\$	\$
2.	Mill Asphalt Conc. Pavement, 3" Depth	SY	81,179	\$	\$
3.	Recycled Asphalt Conc., 19mm Superpave, Incl. Bitum. Material, H Lime & Tack Coat	Ton	8,697	\$	\$
4.	Recycled Asphalt Conc., 12.5mm, GP 2 Superpave, Incl. Bitum. Material, H Lime & Tack Coat	Ton	6,791	\$	\$
5.	Recycled Asphalt Conc. Patching, Incl. Bitum. Material, H Lime & Tack	Ton	1,490	\$	\$
6.	Full Depth Reclamation	SY	5,475	\$	\$
7.	Graded Aggregate Base	TN	170	\$	\$
8.	Recycled Asphalt Conc. Leveling, Incl. Bitum. Material & H Lime	TN	604	\$	\$
9.	6' x 40' Traffic Signal Loop	EA	3	\$	\$
10.	Thermo. Solid Traffic Stripe, 5 IN, Yellow	LF	54,000	\$	\$
11.	Thermo. Solid Traffic Stripe, 5 IN, White	LF	54,000	\$	\$
12.	Thermo. Solid Traffic Stripe, 12 IN, White	LF	1,805	\$	\$
13.	Thermo. Solid Traffic Stripe, 24 IN, White	LF	83	\$	\$
14.	Thermo. Pvmt. Marking, Arrow, TP 2	EA	10	\$	\$
15.	Thermo. Pvmt. Marking, Arrow, TP 3	EA	5	\$	\$
16.	Raised Pavement Markers, TP 1 & 3	EA	1,370	\$	\$
	of discrepancy between the unit price and t	he total pri	ice on the completed	d Bid Schedule, the unit	
price will p	ce will prevail, and the total price will be corrected. TOTAL COST				